

Glencrest Drive / Knottingham Drive Stormwater Improvement Project



Before



After

Purpose:

This project addressed the long history of drainage problems in the Knottingham Drive, Marsha Court, Glencrest Drive, and Crestview Drive area. Many properties experienced erosion and structure flooding from surface drainage issues caused by lack of an adequate conveyance system.

Project Details:

The Glencrest Drive (HU-17) of Group 3 Watershed included installation of approximately 1,450 LF of storm drain pipe and inlet and outlet structures. Work also includes replacement of concrete curb and gutter, sidewalk, driveways, asphalt paving, and other associated construction items along sections of Marsha Court, Glencrest Drive, Crestview, and Knottingham Drive.

<u>Phase</u>	<u>Agenda Date</u>	<u>Funding Source</u>	<u>Budget</u>	<u>Actual</u>	<u>Begin Date</u>	<u>End Date</u>
Concept	Dec-10	SPLOST 2005	\$133,594	\$97,527	Dec-10	Jan-11
PE Design	Sep-11	SPLOST 2005	\$112,602	\$112,602	Mar-12	Mar-13
FE Design						
ROW	Sep-11	SPLOST 2005	\$13,544	\$6,356	Mar-12	Mar-12
Construction*	Oct-12	SPLOST 2005	\$414,088	\$385,317	May-13	Nov-13

Concept: Arcadis David Clark
 Design: Arcadis David Clark
 Construction: Strickland & Sons David Ayers, Rani Katreeb
 Notes: *Ashton Drive (Group 1) and Glencrest projects shared PO 20222, for construction done by Strickland & Sons
 Project: HU-17

**This project is a sub-project of the Stormwater Improvement Group 3: System Improvements project. The sub-project is combined with Group 3 projects on early agenda items. This project was also called "Glencrest, Crestview, Marsha Ct & Knottingham."*